

El Granada Eucalyptus Tree Removal Project

Eucalyptus trees to be removed or thinned out.

Highest Priority within circle areas (C-1 & C-2) in descending order

- Cut and remove all trees within circle areas.
- Grind stump 12" below ground level.
- All tree debris to be removed and disposed as part of contract.

Secondary Priority within rectangular areas (R-1 thru R-4) in descending order

- R-1 thru R-4: Prune & remove all limbs 2" dia. and above that extend over Ave Cabrillo & The Alameda.
- R-1 thru R-4: Prune & remove all large dead limbs 2" dia. and above.
- R-3: Cut & remove dead and dying trees (less than 30% vigor).
- R-2: Cut & remove dead and dying trees (less than 30% vigor).
- R-4: Cut & remove dead and dying trees (less than 30% vigor).
- R-1: Cut & remove dead and dying trees (less than 30% vigor).
- Grind stump 12" below ground level.
- All tree debris to be removed and disposed as part of contract.

